
REPUBLIC OF MOLDOVA

MOLDOVA RURAL CONNECTIVITY PROJECT - P180153

NATIONAL ROAD ADMINISTRATION

AMENDMENT No. 6

to the Request for Bids

Rehabilitation Works on Corridor 24:

Lot 1: Contract MRCP/W2/01:

***Road G133: G132 – Tartaul – Gotești – R34, km 0+000 - km 14+920
(Section 1) and Road G132: R35 – Baimaclia – Taraclia de Salcie –
R32, km 14+220 - km 20+350 (Section 2)***

Lot 2: Contract MRCP/W2/02:

***Road G131: R35 - Bobocica - G132, km 0+000 - km 12+000 (Section 1)
and Road G131: R35 – Bobocica - G132, km 12+000-km 22+110
(Section 2)***

Issued on September 10, 2026

General:

The following amendment articles are applicable to the Request for Bids Document No. **MRCP/W2/01-02:**

Lot 1: Contract MRCP/W2/01: Road G133: G132 – Tartaul – Gotești – R34, km 0+000 - km 14+920 (Section 1) and Road G132: R35 – Baimaclia – Taraclia de Salcie – R32, km 14+220 - km 20+350 (Section 2).

Lot 2: Contract MRCP/W2/02: Road G131: R35 - Bobocica - G132, km 0+000 - km 12+000 (Section 1) and Road G131: R35 – Bobocica - G132, km 12+000-km 22+110 (Section 2).

Article 1

In Section IV - Bidding Forms, link for Bill of Quantities, Lot 1, is deleted and replaced with the updated one as follows:

http://files.asd.md/PIU_WB/BOQ_C24 Lot1 ver.3.4_07.05_Revised_FINAL.zip

Article 2

Request for Bids, Technical Specifications, Chapter 307, Sub-Chapter 307.010 - Works Acceptance, Payment, has been amended to read as follows:

The works measured as indicated above and certified by the Engineer will be paid at the rates provided in the contract against those items that are shown in the bid schedule.

Payment for asphalt works shall be made in accordance with the BOQ Items specified in Section 305 of this Specification.

The payment under these items shall be the whole of the payment due for the completion of all works indicated in the present chapter. Payment will be made under the item below: at the payment of pavement layer, shall be considered also the connecting layers.

Sett Paving shall be carried out in accordance with the requirements of the approved Construction Drawings.

Payment for Sett paving works shall be inclusive of all associated works including preparation of the under-laying supporting layers and the provision, placement and finishing of the Sett paving works.

Item No.	Item description	Unit of Measure
30702	Wearing course of asphalt concrete BA16 with polymer modified bitumen PMB 45/80-80, h-40mm Strat de uzura din beton asfaltic BA16 cu bitum modificat polimeric PMB 45/80-80, grosimea 40mm	Square meter

Article 3

Request for Bids, Bill of Quantities, Lot 1, Section 2, Bill No. 400.2 - BRIDGES, S.2, G133, km 0+000 - 14+920, Bridge Approach, the description of Item No. 41101 has been amended to read as follows:

Item No.	Item description	Unit of Measure
41101	Furnishing and assembling of bridge type steel guardrails H2 W4 Furnizarea si instalarea parapetelor de siguranta pentru poduri H2 W4	Linear meter

Article 4

Request for Bids, Bill of Quantities, Lot 1, Section 1, Bill No. 500 Drainage Structures, the quantity for Item No. 50307 has been changed to read as follows:

Item No.	Item description	Unit of Measure	Quantity
50307	Construct chute entry gulley, single sided Construcția gurii de scurgere dintr-o singură parte la intrarea în casiu	pcs / buc.	64

Article 5

Request for Bids, Bill of Quantities, Lot 1, Section 1, Bill No. 200 Earthworks, the description of Item No. 90105.1 has been amended to read as follows:

Item No.	Item description	Unit of Measure
90105.1	Geogrid Tc-min 100 kN/m Geogrid Tc-min 100 kN/m	m ²

Article 6

Request for Bids, Bill of Quantities, Lot 1, Section 2, Bill No. 500 Drainage Structures, a new item No. 50105.3a – Pipe culverts Ø1,250 mm, has been added as follows:

Item No.	Item description	Unit of Measure	Quantity
50105.3a	Pipe culverts Ø1,250 mm Podețe tubulare Ø 1 250 mm	L.m. / m.l.	16.70

Article 7

Request for Bids, Technical Specifications, CHAPTER 509. DRAINS, MANHOLES, EXIT GULLY, sub-chapter 509.04. Works acceptance, Payment, items No. 50901.1 and No. 50901.2 are provided with full materials requirements for pellicle /membrane as follows:

Item No.	Item description	Unit of Measure
50901.1*	Construction of transversal drains	Linear meter
50901.2*	Construction of longitudinal drains	Linear meter

* For items No. 50901.1 and No. 50901.2, the pellicle shall consist of a polyethylene membrane with a thickness of 0,15-0,20 mm.

Article 8

In Section II: Bid Data Sheet (BDS). ITB 18.1, the following text shall be deleted:

“The Bid shall be valid until: February 13th, 2027”

and replaced with the following text:

“The Bid shall be valid until: March 07th, 2027”

Article 9

In Section II: Bid Data Sheet (BDS). ITB 22.1, the following text shall be deleted:

“Date: September 16th, 2026”,

and replaced with the following text:

“Date: October 08th, 2026”.

Article 10

In Section II: Bid Data Sheet (BDS). ITB 25.1, the following text shall be deleted:

“Date: September 16th, 2026”,

and replaced with the following text:

“Date: October 08th, 2026”